



The "icon" of nuclear power in Sweden



The beginning and the end



Type: BWR
Capacity: 1800 MWt / 615MWe

First connection to the grid: May 15, 1975 / March 21, 1977

Contractor: ASEA Atom (Westinghouse Electric Sweden)

Production, unit 1: Total 93,4 TWh net (1999)

Production, unit 2: Total 108 TWh net (2005)


Status, unit 1: permanently shutdown since 30 Nov 1999

Status, unit 2: permanently shutdown since 31 May 2005

Shutdown activities

Dismantling


Demolition



Barsebäck Conditions

- Swedish management system for operational waste can be used for dismantling waste.
- Repository ready 2028
- Fuel and control-rods are transported to the interim storage
- Clean plant, few fuel leakages
- Time to make studies in the planning process
- Dismantling of unit 1 and 2 will be carried out as a joint project
- Good dialogue with the authorities
- Co-operation in national and international forums to get experience and knowledge
- Compensation for Service operation and Available funds

Planning highlights:



The Licence cover all steps The Safety Analyse Report have to be developed for each step


Studies conducted for the decommissioning

- Cost estimate for the decommissioning
- Dismantling and removal of the entire reactor vessel
- Segmentation of the reactor pressure vessel and internal parts
- Radioactive inventory of Barsebäck 1 and 2
- Mapping of radioactive contamination Part 1
- Disposal of large turbine components
- Demolition of the reactor building
- Demolition of the turbine building and other buildings
- 3D model comprising land and buildings
- Dismantling and waste logistics

Lessons learned and strategy

- Appropriate requirements and regulations
- Available funds and estimated costs
- Available spent fuel storage
- Available radioactive waste storage
- Perform a site characterization of high quality
- Maintain the “Safety-first” culture and focus on risk management.
- Dismantle in big pieces and use proven methods
- Carry out the dismantling on an industrial scale with logistic for “rip and ship”
- Keep control of the project within your own organization
- Involve stakeholders

Right now



- Building interim storage, ready in June -16
- Segmentation of the internal reactor parts starts in the summer of 2016
- Segmentation finished 2019
- Waste management – handling operational waste
- New security equipment installed
- Removal of fuel racks
- Exciting to do something for real!

Thank you for your
attention!



Ongoing and *planned tasks*

- Determination of requirements for demolition and clearance
- Control program for the release
- *Service systems during the dismantling and demolition*
- *Decontamination of pipes and tanks of the waste facility*
- *Mapping of radioactive contamination Part 2*
- *Starting up the application for regulatory permits*

Projects

- Removal of fuel
- Adapting the plant to the service operation
- Full system decontamination
- Removal of control rods and probes
- Removal of the fuel racks
- Processing of waste from operation
- Segmentation and storage of the RPV internals, project HINT

Procedure for Free Released Site

